

Target:

Consolidation and leveling of an industrial broken concrete floor. No stop industrial production was requested.

Previous drilling phase



Copyright ©Prematek Srl

Resin injection phase



Copyright ©Prematek Srl

Maximum lifted point: 7,5 cm



Copyright ©Prematek Srl

Nonstop monitoring phase



Copyright ©Prematek Srl

Solution:

Polyurethane expanding resin injection through a range of holes using packers.

Result:

Floor consolidated and placed at the level; lifted until a maximum score of 7,5 centimeters.

Final result



Copyright ©Prematek Srl